G036 Spec Sheet: Truck/Van Installation of Pure View Mainline System

- **ECO Star System Control Unit:** professional-grade control unit, rack-mounted circuit boards, (2) joysticks, pushbuttons, overlay board, integrated diagnostic system.

- **ELKA600:** cable reel mounted on rack with drawer and slide, motorized and synchronized, telescopic swivel crane with integrated electric chain hoist, cable guiding system, 1,000 ft camera cable with military-style connector.

- **L135:** steerable camera tractor, integrated rearview camera, electric lift, inclination, anti-flipping feature, direct drive (no chains or belts), rubber wheel sets for 8- & 10-inch pipe diameter, 33KHz or 512Hz sonde.

- **Pure View:** 3-D mainline camera, for 8- & 10-inch pipe diameter.

- **Maintenance & Tool kits:** required metric tool kit, spare parts kit.

- **Desktop PC:** industrial grade, current technology and features, rack-mounted, main monitor & PC monitor, printer.

- **Inspection Software:** POSM Pro software, NASSCO-certified, POSM 360 software module, Inclination, 1-year service contract included.

- **Installation:** ceiling and siding panels, insulated, complete electrical wiring, receptacles, lighting, cabinetry, storage, workbench with tool chest, 15-gal wash-down system, Rhino-lined floor, A/C unit with heating strip roof-mounted.

- **Generator:** 5500W ONAN Generator with remote start, transfer switch, 25ft shoreline, battery, connected to vehicle fuel line, fuel pump.

- **Training:** 3 days of training at customer's location.